



### Section 7

### ALI Focal Plane Technology

MIT-LL Subcontract No. BX-6283

... Karl Blasius

Raytheon Santa Barbara Remote Sensing

... Clifford Nichols

Raytheon Infrared Operations





## Raytheon Provided the ALI Focal Plane System (FPS)



- Combined Effort of Santa Barbara Remote Sensing (lead) and Raytheon Infrared Operations, Goleta, CA
- ◆ FPS was designed and developed from June 1996 to June 1998
- ◆ FPS was delivered to MIT-LL on June 18th, 1998





### Raytheon's ALI Focal Plane System




#### Technologies Advanced in Maturity to Benefit Future Science Missions with Reduced Risk

- ◆ Advanced 2nd-generation CMOS readout ICs
- Small (13.2X13.2 μm and 40X40 μm) pixels, high-density Sensor Chip Assemblies (SCAs)
- Monolithic Si VNIR detector elements
- ♦ High operating temperature (220 K) SWIR (2.5 μm wavelength cutoff) HgCdTe detector arrays
- High-density edge-bonded MS/PAN filter assemblies



7 - 3




### Focal Plane System in ALI




#### Focal Plane System Elements

- Focal Plane Assembly
- Focal Plane Electronics



**Focal Plane Electronics (FPE)** 






## Earth Observing-1

# ALI FPS Demonstrates ~5 X Performance Improvement Over Landsat 7



## Signal-to-Noise Ratios @ 5% Earth Surface Reflectance



Band	W avelength (m m )	Detector Type	GSD (m)	# Detectors
Pan	0.480-0.680	SiPhotodiode	10	3840
M S -1'	0.433-0.453	SiPhotodiode	30	
M S -1'	0.450-0.515			
M S -2	0.525-0.605			1280
M S -3	0.630-0.690			PerBand
M S -4	0.775-0.805			
M S -4'	0.845-0.890			
M S -5 '	1.200-1.300	PV HgC dTe	30	1280
M S -5 '	1.550-1.750			PerBand
M S -7	2.080-2.350			reiballu

- ◆ FPA operates at the "warm" temperature of 220 K
- Nominal sample rates:
  - 226 Hz (VNIR, SWIR)
  - 678 Hz (PAN)
- 4,096 selectable sample rates (to accommodate for altitude variation)
- Adjustable integration duty cycle (to accommodate scene level)
- SNRs shown (see bar chart) acquired at 5 % of maximum scene irradiance
- Standard Landsat bands (PAN, 1, 2, 3, 4, 5, 7) and experimental bands (1', 4', 5') support both L7 comparison and new science




**7 - 5** 



## Multispectral/Panchromatic VIS-SWIR FPA





Main Focal Plane Assembly in Handling Fixture

- FPS performance exceeded both program specs and prior LANDSAT performance levels
- FPA designed to support five (5) MS/PAN modules for future Landsat missions (15° swath coverage)
- Demo program called for partially-populated FPA, one module with detectors
- Integrated with flight telescope at MIT-LL in Summer 1998





## MS/PAN Module Meets or Exceeds all Specifications



- Responsitivities optimized for each band to satisfy flux range requirements
- SNR meets program specs with an average of 50 % performance margin!
- 99.94 % measured operability meets spec with dramatic margin
  - 9 "inoperable" pixels
  - 15,360 total pixels on MS/PAN module
- Excellent radiometric uniformity and sensitivity, even for high-resolution 13.2 μm x 13.2 μm panchromatic (PAN) pixels
- High operating temperature (220 K)
- Low power (~ 300 mW/module)
- Stable response vs. temporal and thermal variation










### MS/PAN Module Subassembly



(shown with filter-bezel removed)




- Flight module shown mounted in assembly tooling fixture
- ♦ 4 SCAs per module
- Multi-layer ceramic motherboard
- ◆ Beryllium pedestal
- ◆ 16-inch cryo cable
- ♦ 18 bypass capacitors
- ◆ 1 temperature sensor



## MS/PAN Spectral Filter-Bezel Assemblies





- Four filter assemblies per module (one per SCA)
- 10-piece edge-bonded,
   "butcher block" filter
   assemblies
  - Dark Mirror Coating (DMC) defines clear apertures
  - Edge coatings for optical baffling
- Filter assemblies bezelmounted as shown
- Excellent transmission, spectral bandpass, and out-of-band rejection characteristics



## MS/PAN Sensor Chip Assembly (SCA)



#### Spectral Bands:

- Panchromatic (PAN)
- 1, 1', 2, 3, 4, 4' (VNIR)
- 5', 5, 7 (SWIR)

#### Array Configurations:

- 2 x 480 (PAN)
- 2 x 160 (VNIR, SWIR)

#### Pixel Dimensions:

- (13.2 x 13.2) μm (PAN)
- (39.6 x 40.0)  $\mu$ m (VNIR, SWIR)

#### **♦ CMOS CTIA ROIC**

(Orbit 1.2 μm, rad-tol. process)

#### Detector Materials:


- Monolithic Si (PAN, VNIR)
- SWIR HgCdTe (SWIR)

#### Monolithic Si Detectors

- Built directly into ROIC
- optically delineated with metal and DMC

#### ◆ SWIR HgCdTe Detector Array

- 2.5 μm cutoff wavelength
- Fully-redundant detector select









## FPS Delivered with Ground Support Equipment










## FPS Delivered with Ground Support Equipment Mission Technology Forum







## ALI FPA Fully Populated for Future Landsat Mission



- ◆ Populate Focal Plane with Five MS-PAN Modules
  - Full 185 km wide field-of-view
  - Main focal plane bench designed for five modules



#### ◆ Changes required to accommodate full 185 km MS-PAN coverage

Resource	ALI	Advanced Landsat
<b>Data Ports</b>	1	5
Data Rate	102.4 Mb/sec	512 Mb/sec
FPE Power	~15 Watts	~50 Watts
FPA Size	30.7 X 6.6 X 5.2 cm	30.7 X 6.6 X 5.2 cm



7 - 13